

DEPARTMENT NAME	SRI POTTI SRI RAMULU NELLORE DISTRICT, CO-OPERATIVE CENTRAL BANK LIMITED, NELLORE
NAME OF THE WORK	CONSTRUCTION OF D.C.C.B COMPOUND WALL AT KUMMARAGUNTA, VENKATAGIRI, TIRUPATI DISTRICT
ESTIMATED CONTRACT VALUE(INR)	RS. 24,15,076/- (RUPEES TWENTY FOUR LAKH FIFTEEN THOUSAND AND SEVENTY SIX ONLY)
PERIOD OF COMPLETION	3 MONTHS
FORM OF CONTRACT	L.S
BIDDING TYPE	OPEN
BID CALL(NOS)	1
GST	18%

DETAILS OF TENDER

COST OF TENDER SCHEDULE : Rs. 1000/- + GST@18%

EMD

EMD at the time of tender @ 1% : Rs. 25,000/-

EMD at the time of awarding contract@ 1.5% : Rs. 37,000/-

EMD DD DRAWN IN FAVOUR OF : **CHIEF EXECUTIVE OFFICER**, SPSR NDCC
BANK, NELLORE

TENDER DATES

ISSUE OF TENDER SCHEDULE DATE : 27-07-2026

LAST DATE OF TENDER : 05-08-2026 @ 03.00 PM

DATE OF OPENING TENDER : 05-08-2026 @ 04.00 PM

**Name of the work: Construction of D.C.C.B Compound Wall at S. No. 185-A, Kummaragunta, Venkatagiri,
Tirupati District**

Total Estimate cost Rs. 24.15 Lakh

Sl. No	Probable quantity both in fig & words	Description of item	Unit of measurement both in fig& words	Rate both in fig& words	Amount in Rupees
1	2	3	4	5	6
1	23.82 cum Twenty three point Eighty Two cubic meters only	Earthwork in excavation for foundation in all kinds of soil except rock requiring blasting including cost and conveyance of all materials and labour charges etc.	1 CUM (One Cubic Meter only)	1,800.00 (Rupees One Thousand Eight Hundred only)	42,871.00
2	45.09 cum Forty Five point Zero Nine cubic meters only	P.C.C Bed (1:4:8) using 40 mm HBG metal for foundation bed including cost and conveyance of all materials and labour charges etc.	1 CUM (One Cubic Meter only)	2,000.00 (Rupees Two Thousand only)	90,186.00
3	15.60 cum Fifteen point Six Zero cubic meters only	R.C.C Bed (1:1:5:3) using 20 mm HBG metal for using 40Kgs of Tor Steel per cum of concrete for supported columns for piles including cost and conveyance of all materials and labour charges etc.	1 CUM (One Cubic Meter only)	24,500.00 (Rupees Twenty Four Thousand Five Hundred only)	3,82,308.00
4	13.57 cum Thirteen Point Five Seven cubic meters only	R.C.C Bed (1:1:5:3) using 20 mm HBG metal for using 40Kgs of Tor Steel per cum of concrete for supported columns including cost and conveyance of all materials and labour charges etc.	1 CUM (One Cubic Meter only)	24,500.00 (Rupees Twenty Four Thousand Five Hundred only)	3,32,374.00

5	18.26 cum Eighteen point Two Six cubic meters only	R.C.C Bed (1:2:4) using 20 mm HBG metal for using 80Kgs of Tor Steel per cum of concrete for “plinth beams” including cost and conveyance of all materials and labour charges etc.	1 CUM (One Cubic Meter only)	24,500.00 (Rupees Twenty Four Thousand Five Hundred only)	4,47,357.00
6	71.45 cum Seventy One point Four Five cubic meters only	Brick work in cm (1:6) using well burnt country bricks for “Basement” including cost and conveyance of all materials and labour charges etc.	1 CUM (One Cubic Meter only)	6,000.00 (Rupees Six Thousand only)	4,28,701.00
7	92.51 cum Ninety Two point Five One cubic meters only	Brick work in cm (1:6) using AAC Blocks for “super structure” including cost and conveyance of all materials and labour charges etc.	1 CUM (One Cubic Meter only)	4,000.00 (Rupees Six Thousand only)	3,70,059.00
8	563.51 Sq. M Five Hundred Sixty Three point Fifty One square meters only	Plastering with CM(1:5), using 12/20 mm thick for walls including cost and conveyance of all materials and labour charges etc.	10 SQM (Ten square meters only)	450.00 (Rupees Four Hundred Fifty only)	2,53,581.00
9	563.66 Sq. M Five Hundred Sixty Three point Six Six square meters only	White wash for wall with a double coating including cost and conveyance of all materials and labour charges etc.	10 SQM (Ten square meters only)	120.00 (Rupees One Hundred Twenty only)	67,639.00
		Total No. of Items 9 (Nine only)			24,15,076.00